


PROPOSED RESIDENTIAL DRIVEWAY ON CORNER LOT WITH SIDE YARD



PROPOSED RESIDENTIAL DRIVEWAY ON CORNER LOT WITH SIDE YARD GARAGE

NOTES:

1. NO RADIUS OR RAISED CURBS ON CITY RIGHT OF WAY. STRAIGHT FLARES ONLY.
 2. NOTWITHSTANDING THIS DRAWING, CURB CUT WIDTH SHALL NOT EXCEED 50% OF FRONTAGE WIDTH.
 3. NEW DRIVEWAYS FOR HOMES ON CORNER LOTS SHALL BE CONSTRUCTED ON THE SIDE OF THE HOUSE OPPOSITE OF THE INTERSECTION.
- * DRIVEWAY PORTION ON PRIVATE PROPERTY IS TO COMPLY WITH AND BE APPROVED BY THE BUILDING DEPARTMENT AT THE CITY OF WINDSOR.
- DRIVEWAY MUST HAVE A MINIMUM SEPARATION OF 0.9m (3') OF ANY VERTICAL OBSTRUCTION. ie. HYDRO POLE, FIRE HYDRANT, CABLE BOX, TREE, ETC.

CITY OF WINDSOR	
ENGINEERING DEPARTMENT	
Maximum Curb Cut For Residential Driveways on Corner Lots	
DR'N BY: AJC, JL	DATE: JANUARY, 2011
REVISION: NOV, 2013	CH'KD BY: P. UBENE
CH'KD BY: SS	PASSED BY:
<i>[Signature]</i> CITY ENGINEER	AS-542-B