



**THE CORPORATION OF THE CITY OF WINDSOR
OFFICE OF THE CITY SOLICITOR**

ALEX VUCINIC
Manager of Purchasing

Elaine Castellan
Purchasing Supervisor

(519) 255-6272
TELEPHONE NUMBER

**ADDENDUM NO. 4
TENDER NO. 24-19
BRUCE AVENUE PARK REDEVELOPMENT**

May 15, 2019

This addendum amends and forms part of the Tender Documents. The bidder shall insert the addendum behind the cover page of the Tender Documents.

QUESTION & ANSWER:

1. In Addendum 3, Question 3, it states that there is only to be one (1) Code Blue Call station but Bid Form-Price Schedule, Item # 71, still states three (3). Can you please confirm the quantity required?

Quantity should read as one (1). Please see revised Bid Form – Price Schedule Addendum #4, which must be used for bid submission.

Except for the contents of this addendum, all other terms and conditions of this tender remain the same.

END OF ADDENDUM NO. 4

Yours truly,

THE CORPORATION OF THE CITY OF WINDSOR

Elaine Castellan

Elaine Castellan
Purchasing Supervisor

EC/sf

**ADDENDUM NO. 4
TENDER NO. 24-19
BRUCE AVENUE PARK REDEVELOPMENT**

May 15, 2019

I hereby acknowledge receipt of Addendum No. 4 to the Tender No. 24-19 (12 pages).

The information contained therein is hereby noted and account of same will be taken in our tender cost.

This information was received on the _____ day of _____, 20_____.

Signature

Name (Printed)

Company Name

***NOTE: You are required to acknowledge this addendum with your TENDER submission.**

**PLEASE FAX BACK TO (519) 255-9891 OR E-MAIL @ purchasing@citywindsor.ca SIGNED
ACKNOWLEDGEMENT SHEET ASAP**

Attn: Purchasing Department

BRUCE AVENUE PARK REDEVELOPMENT

Addendum #4

BID FORM – PRICE SCHEDULE

ITEM #	ITEM DESCRIPTION	ESTIMATED QUANTITY (MORE OR LESS)	UNIT OF MEASURE	UNIT PRICE	EXTENDED TOTAL
<u>DEMOLITION / REMOVAL AND DISPOSAL</u>					
1	Remove and dispose of off-site all existing asphalt as indicated on drawings including existing pathways and basketball court area	1584	M2		
2	Remove existing base for pathway and asphalt areas including existing basketball court area and driveway off church street and dispose of off site	1669	M2		
3	Remove and dispose of off-site 1 existing bollard (wooden) 2 footings	1	Lump Sum		
4	Saw cut where necessary, remove and dispose of off-site existing concrete around playground as indicated on drawings-NOTE: leave perimeter curb in dowl into new concrete areas	40	M2		
5	Remove and Relocate 4 benches and 1 Bike Rack Supply stainless steel hardware surface mount on new Concrete pad	5	Each		
6	Remove and dispose off-site existing soil/ fill as identified on drawings to the grades and depths as indicated on drawings	3043	CY		
7	Remove and dispose off-site existing community garden area vegetation wood and debris	500	M2		

BRUCE AVENUE PARK REDEVELOPMENT

Addendum #4

ITEM #	ITEM DESCRIPTION	ESTIMATED QUANTITY (MORE OR LESS)	UNIT OF MEASURE	UNIT PRICE	EXTENDED TOTAL
8	Remove and dispose of off-site existing concrete paver walkway along alley	210	M2		
9	Remove and dispose of off-site the existing building, 1 shed, and storage box, all footings, concrete surrounding the building and backfill with clean fill include all permits required in this cost	1	Lump Sum		
10	Remove and dispose of off-site the existing shelter and concrete pad backfill with clean fill	1	Lump Sum		
11	Remove and dispose of off-site existing basketball pole standard	1	Each		
12	Grind out Remove and dispose of off-site existing tree stumps. Stumps must be ground 1' below grade	25	Each		
13	Disconnect Remove and dispose of existing light pole. Dismount lights bring to parks main yard	2	Each		
14	Relocated 1 Yellow Sharp Box on Existing Concrete Pad	1	Each		
15	Remove existing gravel walkway South west of playground (re-use) stone for new pathway base	206	M2		
16	Remove and dispose of off-site existing Car Planter and chain link fence as indicated on drawings grub and clear fence line	1	Lump Sum		

BRUCE AVENUE PARK REDEVELOPMENT

Addendum #4

ITEM #	ITEM DESCRIPTION	ESTIMATED QUANTITY (MORE OR LESS)	UNIT OF MEASURE	UNIT PRICE	EXTENDED TOTAL
17	Remove and Relocate in ground trash and recycling containers	3	Each		
18	Remove and dispose of off-site existing signs and concrete pad Bring community garden sign and pedestal back to main parks yard at 2450 McDougall parks	1	Lump Sum		
<u>ASPHALT PATHWAY CONSTRUCTION / ASPHALT SPORTS COURT</u>					
19	Excavate topsoil to clay for entire length of pathway as indicated on drawings approx. 18" depth	731	M3		
20	Supply, place, roll and compact Granular "A" base course for pathway compact to 100% S.P.D	1440	Tonnes		
21	Supply, place and compact HL3 surface asphalt for pathway 75mm thick x 1624m x 3m wide.	327	Tonnes		
22	Excavate entire sports court areas as indicated on drawings to clay approx. 450mm (18") deep	248	M3		
23	Supply, place, roll and compact Granular 'A' base course for new sports court compact to 100% S.P.D	458	Tonnes		

BRUCE AVENUE PARK REDEVELOPMENT

Addendum #4

ITEM #	ITEM DESCRIPTION	ESTIMATED QUANTITY (MORE OR LESS)	UNIT OF MEASURE	UNIT PRICE	EXTENDED TOTAL
24	Supply place roll and compact HL3 surface asphalt for sports court as indicated on drawings 75mm thick x 30.78M x17.6M	102	Tonnes		
25	Supply place and compact Granular 'A' base around perimeter of sports court under concrete apron 150mm x96Mx.6M	17	Tonnes		
26	Supply all labour and material to excavate, supply and place new concrete for apron around perimeter of sports court including 6 sonotubes 450mm x 96Mx.6M	35	CY		
27	Supply and place new 4" Big-'O' with sock around perimeter of new sports court. Tie into existing CB in alley include all permits	105	LM		
28	Supply all labour and material to install Multi-purpose cushioned surface colour coating system premium complete with all lines and colours as indicated on drawing and specifications see spec sections for more detail	1	Lump Sum		
29	Supply all labour and material to install black vinyl 3M high chain link fencing around perimeter of basketball court perimeter with 2 man gates and 1 maintenance entrance as per details	95	LM		

BRUCE AVENUE PARK REDEVELOPMENT

Addendum #4

ITEM #	ITEM DESCRIPTION	ESTIMATED QUANTITY (MORE OR LESS)	UNIT OF MEASURE	UNIT PRICE	EXTENDED TOTAL
30	Construct concrete entrance approach as per drawings for 7 locations set dome tactile plate in as per drawings	45	M2		
31	Supply and Install 2- 50mm(2") SOLID PVC conduits under pathways at 8 locations as indicated on drawings	16	Each		
32	Supply and Install 1- 100mm (4") SOLID PVC conduit under pathways at 8 locations as indicated on drawings	8	Each		
33	Supply and install new Basketball post system as per drawings and specifications or approved equal	2	Each		
34	Supply and install new 2- 50mm (2") Solid PVC conduits stub up in concrete as indicated on drawings one for shelter electrical one for storage building electrical	2	Each		
35	Supply and Install (crane) new Pre-cast storage shed building on new concrete slab see spec sections for details 10'x18'	1	Lump Sum		
36	Supply and Install new In ground Garbage and recycling Containers as per drawings and specs	8	Each		

BRUCE AVENUE PARK REDEVELOPMENT

Addendum #4

ITEM #	ITEM DESCRIPTION	ESTIMATED QUANTITY (MORE OR LESS)	UNIT OF MEASURE	UNIT PRICE	EXTENDED TOTAL
37	Supply and install cast-in place- truncated dome tactile surface indicators at entrance locations as indicated in the drawings 0.6Mx1.21M (2'x4') mats	16	Each		
<u>CONCRETE FLATWORK</u>					
38	Excavate topsoil to clay in areas designated on drawings for concrete plaza including shelter and sidewalk by sports court (excluding community garden)	361	M3		
39	Supply, place, and compact Granular "A" base under concrete area as designated on drawings for the plaza/shelter and sidewalk by sports court (excluding community garden) roll and compact to 100% S.P.D estimated depth approx. 457mm (18")	842	Tonnes		
40	Supply all labour and material to install 127mm (5") thick concrete plaza/walkways as indicated on drawings (not including thickened shelter pad) (bench pads separate)	740	M2		
41	Supply 4 concrete footings for new Shelter as per drawings and specifications	4	Each		
42	Supply all labour and material for thickened concrete shelter pad as per drawings and specifications include coloured concrete band	84	M2		
43	Supply all labour and material to install 15 concrete bench pads 1.5Mx3.65M (5'x12') with integral curb stop for wheelchairs see details	15	Each		

BRUCE AVENUE PARK REDEVELOPMENT

Addendum #4

ITEM #	ITEM DESCRIPTION	ESTIMATED QUANTITY (MORE OR LESS)	UNIT OF MEASURE	UNIT PRICE	EXTENDED TOTAL
44	Supply all labour material permits and Canadian stamped engineering drawings to supply 1 shelter as per drawings and specifications or approved equal	1	Each	\$180,000.00	\$180,000.00
45	Supply all labour material to install new barrier curb where driveway approach was removed	4	LM		
<u>GRADING / DRAINAGE</u>					
46	Supply all labour and material to place topsoil re-grade soccer field and finish grade entire park as indicated on drawings (#2 topsoil)	8838	M2		
47	Supply and install C.O.W. Standard Catch basin w/frame and cover 24"x24" as indicated on drawings	5	Each		
48	Supply and install 150mm (6") Big 'O' around exterior of soccer field and on south side of park as indicated on drawings connect to new CB	150	LM		
49	Supply and install 150mm (6") solid PVC pipe and connect to new CB as indicated on drawings Contractor to ensure positive drainage	191	LM		
50	Flush and clean out all existing CB and MH in park. Ensure all new and existing CB in the park are clear and operable at project close use filter cloth to prevent new soil from washing	1	Lump Sum		

BRUCE AVENUE PARK REDEVELOPMENT

Addendum #4

ITEM #	ITEM DESCRIPTION	ESTIMATED QUANTITY (MORE OR LESS)	UNIT OF MEASURE	UNIT PRICE	EXTENDED TOTAL
51	Supply permits necessary to tap MH in Alley	1	Lump Sum		
<u>LANDSCAPING/ FENCING</u>					
52	Supply all labour and material to fine grade prepare and Sod areas as indicated on drawings	1723	M2		
53	Supply all labour and material to fine grade prepare and hydroseed areas as indicated on drawings	8029	M2		
54	Grub and clear property lines around perimeter of park. Remove and dispose of off site all stumps debris garbage as necessary	1	Lump Sum		
55	Remove fabric on chain link fencing around perimeter of park as indicated	160	LM		
56	Supply 1.8M (6') high black vinyl chain link perimeter property line fencing (mesh only) install on existing posts	203	LM		
57	Supply and install all trees as indicated on drawings contractor shall include 1.8M wide x .1524 thick ring of Canada red mulch around each tree. Trees shall be staked and installed according to details and specifications	1	Lump Sum		
58	Supply and install 4' high black vinyl chain link fencing down property along alley and on the south east side of the park as indicated on Landscape plan	155	LM		

BRUCE AVENUE PARK REDEVELOPMENT

Addendum #4

ITEM #	ITEM DESCRIPTION	ESTIMATED QUANTITY (MORE OR LESS)	UNIT OF MEASURE	UNIT PRICE	EXTENDED TOTAL
<u>SITE FURNISHINGS AND FENCING</u>					
59	Pick up 6 steel frame picnic tables from Parks main yard at 2450 McDougall and install on site with stainless steel lag bolts in location as directed by project manager	6	Each		
60	Supply and install new RB-28 Benches as indicated on drawings using all stainless steel lag bolts and hardware	15	Each		
<u>SITE LIGHTING AND EMERGENCY CALL STATIONS</u>					
61	Supply and install ridged ducts (direct Buried) 53mm C Conduits for Communication Conduits for Emergency Call Stations	1	LM		
62	Supply and Install Wiring: Street light wiring (2#6AWG RWU-90) Shelter lights Wiring and Emergency Call Station Wiring (2#6awg RWU-90)	1200	LM		
63	Grounding: #6 bare copper ground wire for street lighting	1120	LM		
64	Ground Rods	7	Each		
65	Ground Plate at Power Supply location	1	Each		
66	Ground Plates for Emergency call stations	1	Lump Sum		
67	"SYNERTECH Junction Box 13"x24"x18"	1	Each		
68	SYNERTECH' Junction Box 12"x12"x12"	5	Each		
69	Park Street Light Luminaire, Shelter lights and Mast Arms To be supplied by the City of Winsor to be picked up at Parks main yard by contractor and assembled	1	Lump Sum		

BRUCE AVENUE PARK REDEVELOPMENT

Addendum #4

ITEM #	ITEM DESCRIPTION	ESTIMATED QUANTITY (MORE OR LESS)	UNIT OF MEASURE	UNIT PRICE	EXTENDED TOTAL
70	Pole Assemblies to be supplied by City of Windsor contractor to erect and install in the park	1	Lump Sum		
71	Supply and install all Emergency Call Stations and related accessories as specified	1	Each		
72	Emergency Call Station Electrical Wiring and communication connections	1	Lump Sum		
73	Power Supply Meter and Disconnect box Combinational Unit as specified	1	Each		
74	Power Supply Conduits, Wiring and Connections	1	Lump Sum		
<u>Miscellaneous / Mobilization Demobilization/ Permits Fees/ Signage</u>					
75	Supply all labour and material for site security including all barricades/snow fencing/ and signage including 5 24"x36" temporary construction signs	1	Lump Sum		
76	Permits/ as built drawings	1	Lump Sum		
77	Tree/Sod Watering for duration of summer after planting has occurred approx. 2 months	1	Lump Sum		
78	Layout by certified surveyor for all park features as indicated on drawings including pathways/ soccer field/ sports court/ shelter etc...	1	Lump Sum		
79	Install stall 1 MH as indicated on drawings make connections to existing infrastructure as per plans see grading plan	1	Each		
80	Mobilization/ Demobilization	1	Lump Sum		
81	Contingency	1	Lump Sum	\$100,000.00	\$100,000.00
TOTAL TENDER PRICE (INCLUDING CONTINGENCY ALLOWANCE, EXCLUDING H.S.T) Enter amount on Bid Form					\$