



**THE CORPORATION OF THE CITY OF WINDSOR
OFFICE OF THE CITY SOLICITOR**

ALEX VUCINIC
Manager of Purchasing

Elaine Castellan
Purchasing Supervisor

(519) 255-6272
TELEPHONE NUMBER

**ADDENDUM NO. 1
PLAYGROUND CONCRETE & SITE WORK – FAZIO PARK
RFT NO. 29-19**

February 12, 2019

This addendum amends and forms part of the Tender Documents. The Bidder shall insert the addendum behind the cover page of the Tender Documents.

QUESTIONS & ANSWERS:

Q1. After reviewing the tender and drawings it does not appear that there is an item for the Earth Excavation. Is it to be included under another item or should there be a separate item for excavation?

The excavation component was omitted in error. Please see the attached new Bid Form “Price Schedule” which has been revised to include the required excavation component of this project.

Addendum No. 1 Bid Form Price Schedule **MUST** be used in the submission for this tender.

Except for the contents of this addendum, all other terms and conditions of this tender remain the same.

END OF ADDENDUM NO. 1

Yours truly,

THE CORPORATION OF THE CITY OF WINDSOR

Alex Vucinic

Alex Vucinic
Purchasing Manager

AV/sf

**ADDENDUM NO. 1
PLAYGROUND CONCRETE & SITE WORK – FAZIO PARK
RFT NO. 29-19**

February 12, 2019

I hereby acknowledge receipt of Addendum No. 1 to the RFT No. 29-19 (4 pages).

The information contained therein is hereby noted and account of same will be taken in our tender cost.

This information was received on the _____ day of _____, 20_____.

Signature

Name (Printed)

Company Name

***NOTE: You are required to acknowledge this addendum with your tender submission.**

**PLEASE FAX BACK TO (519) 255-9891 OR E-MAIL @ purchasing@citywindsor.ca SIGNED
ACKNOWLEDGEMENT SHEET ASAP**

Attn: Purchasing Department

PLAYGROUND CONCRETE & SITE WORK - FAZIO PARK

ADDENDUM NO. 1

BID FORM

PRICE SCHEDULE

FAZIO PARK PLAYGROUND					
SITE WORK					
Item No.	Description	Quantity (More or Less)	Unit of Measure	Unit Price	Extended Total
1).	Supply all labour and material to excavate soil, supply, install and compact 457mm(18") Granular 'A' base for playground including finished grading and compacting to 100% S.P.D. Playground base must be level graded 300mm (12") below top of finished concrete.	347	Tonnes	\$	\$
2).	Supply all labour and material to install 100mm (4") Big O/W sock on the interior of the playground as indicated on drawing and backfill with granular "A" connect to outside drainage.	71	L.M.	\$	\$
3).	Supply all labour and material to install 100mm (4") Big O/W sock and backfill with 3/4" clear stone and connect to existing drainage inlet by the embankment.	15	L.M.	\$	\$
4).	Supply and install 1 solid PVC Sleeve 152mm under new concrete walkway.	7	L.M.	\$	\$
5).	Supply all labour and material to excavate soil, supply and install 300mm (12") Granular 'A' under concrete walkways Compact to 100% S.P.D.	293	Tonnes	\$	\$
6).	Supply all labour and material to install concrete walkways as indicated on drawings 125mm (5") thick including 6x6x6 w.w. mesh broom finish with 100mm (4") border	370	S.M.	\$	\$

PLAYGROUND CONCRETE & SITE WORK - FAZIO PARK

ADDENDUM NO. 1

BID FORM

PRICE SCHEDULE

FAZIO PARK PLAYGROUND					
SITE WORK					
Item No.	Description	Quantity (More or Less)	Unit of Measure	Unit Price	Extended Total
7).	Site layout Surveyor Work (Playground must be laid out exactly as indicated on drawings in order to accommodate playground equipment) Certified Surveyor required.	1	Lump Sum	\$	\$
8).	Mobilization and Demobilization	1	Lump Sum	\$	\$
9).	Site Security Barricades	1	Lump Sum	\$	\$
10).	Contingency Allowance	1	Lump Sum	\$10,000.00	\$10,000.00
TOTAL TENDER PRICE (INCLUDING CONTINGENCY, EXCLUDING HST)					\$

NOTE: It is understood that the quantities listed herein are estimates only. The tenderer is responsible to verify all quantities & report any discrepancies to the owner prior to tender closing date.

 Company Name

 Date