



**THE CORPORATION OF THE CITY OF WINDSOR
OFFICE OF THE CITY SOLICITOR**

ALEX VUCINIC
Manager of Purchasing

Elaine Castellan
Purchasing Supervisor

(519) 255-6272
TELEPHONE NUMBER

**ADDENDUM NO. 3
TENDER NO. 03-21
BERNARD ROAD REHABILITATION**

March 12, 2021

This addendum amends and forms part of the Tender Documents. The bidder shall insert the addendum behind the cover page of the Tender Documents.

CCTV video will not be given out to bidders. Bidders can find the attached CCTV report of this sewer run.

Except for the contents of this addendum, all other terms and conditions of this tender remain the same.

END OF ADDENDUM NO. 3

Yours truly,

THE CORPORATION OF THE CITY OF WINDSOR

Elaine Castellan

Elaine Castellan
Purchasing Supervisor
EC/jm

**ADDENDUM NO. 3
TENDER NO. 03-21
BERNARD ROAD REHABILITATION**

March 12, 2021

I hereby acknowledge receipt of Addendum No. 3 to the Tender No. 03-21 (3 pages).

The information contained therein is hereby noted and account of same will be taken in our tender cost.

This information was received on the _____ day of _____, 20____.

Signature

Name (Printed)

Company Name

***NOTE: You are required to acknowledge this addendum with your TENDER submission.**

**PLEASE E-MAIL @ purchasing@citywindsor.ca SIGNED ACKNOWLEDGEMENT SHEET
ASAP**

Attn: Purchasing Department

Tabular Report of PSR 1D302 X for CITY OF WINDSOR

Setup 1	Surveyor JAMIE LYMAN	Certificate # U-1116-07004424	System Owner
Drainage	Survey Customer		
P/O #	Date 2017/06/05	Time 9:27	Street BERDARD ROAD
City WINDSOR	Further location details		
Up 1D302	Rim to invert	Grade to invert	Rim to grade M
Down 1D49	Rim to invert	Grade to invert	Rim to grade M
Use Stormwater	Direction Down	Flow control	Media No
Shape Circular	Height 250	Width mm	Preclean J
Material Vitrified Clay Pipe	Joint length M	Total length 58.7 M	Length Surveyed 58.7 M
Lining	Year laid	Year rehabilitated	Weather
Purpose	Cat	Pressure	
Additional info		Structural	O & M
Location		Miscellaneous	Constructional
Project	BERNARD ROAD -6/5/2017		Work Order
Northing	Easting	Elevation	
Coordinate System	GPS Accuracy		

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0		ST	Start of Survey							
0.0		AMH	Manhole							1D302
0.0		MWL	Water Level			5				
1.1		CM	Crack Multiple				12	12		
1.6		HSV	Hole Soil Visible				09			
3.6		HVV	Hole Void Visible				02			
4.1		TF	Tap Factory	150			10			
10.3		TF	Tap Factory	150			10			
11.5		MMC	Material change							PVC
58.7		AMH	Manhole							1D49
58.7		FH	End of Survey							

58.7 M Total Length Surveyed

Scores	Structural:	Pipe Rating 13	Pipe Ratings Index 4.3	Peak 5	Mean Pipe 0.2
	O&M:	Pipe Rating 0	Pipe Ratings Index 0	Peak 0	Mean Pipe 0



HURRICANE SMS INC.

Hurricane SMS Inc.
Phone:519-726-6388