



**THE CORPORATION OF THE CITY OF WINDSOR
OFFICE OF THE CITY SOLICITOR**

ALEX VUCINIC
Manager of Purchasing

Elaine Castellan
Purchasing Supervisor

(519) 255-6272
TELEPHONE NUMBER

**ADDENDUM NO. 2
SUMP PUMP REPLACEMENTS – WINDSOR JUSTICE FACILITY
RFT NO. 172-19**

January 13, 2020

This addendum amends and forms part of the Tender Documents. The Bidder shall insert the addendum behind the cover page of the Tender Documents.

SPECIFICATION REVISIONS:

Remove: General Conditions of Service- 1. Commencement Date

Replace with:

General Conditions of Service- “1. Commencement Date

The City’s Project Manager will instruct the successful Bidder to commence work by a date (the “Commencement Date”) not later than the seventh calendar day following the date of issuing the instruction. The Contractor shall commence the work and shall complete it before the expiration of **TWENTY (20)** working days from the commencement date specified in the order. Failing to commence work by the Commencement Date shall be deemed a default under the Contract.”

QUESTIONS & ANSWERS:

Q1. For Pumps 332A and 332B it shows 5hp as per the schedule (below); however the pump model specified WG50-53 is for the 3 HP pump. Can you please confirm if you want the 5hp pump or the 3 hp pump?

332A	D	B234	5	575	3	2-1/2"	Myers	WG50-53	SRA23HH	900x900x2450
332B	D	B234	5	575	3	2-1/2"	Myers	WG50-53	SRA23HH	900x900x2450

A: Pumps 332A, & 332B are specified as 5HP pumps.

Q2. In order to complete this project the water flow must be shutdown to the pits during the removal and replacement. Who is responsible for the shutdown of the sanitary / storm drains to each pit?

a. If it is not possible to shut down the sanitary, how would you like us to proceed?

A: The sanitary sump pits serve only floor drains, and condensate drains on basement levels. The Storm sump pits serve foundation drainage. The Contractor shall assume that work would occur on only a single pit at any given time, and storm pits should be left in service on days when heavy precipitation is forecast. The contractor should also plan to temporarily plug the inlet pipes, and shall have portable pumping equipment available to handle seepage. Notice will be provided by the City of Windsor project manager to building staff

not to introduce significant volumes of water to the floor drains during periods of sanitary pit work. No pit should be taken out of service overnight without suitable provision for temporary pumping.

Except for the contents of this addendum, all other terms and conditions of this tender remain the same.

END OF ADDENDUM NO. 2

Yours truly,

THE CORPORATION OF THE CITY OF WINDSOR

Elaine Castellan

Elaine Castellan
Purchasing Supervisor

EC/ab

**ADDENDUM NO. 2
SUMP PUMP REPLACEMENTS – WINDSOR JUSTICE FACILITY
RFT NO. 172-19**

January 13, 2020

I hereby acknowledge receipt of Addendum No. 2 to Tender No. 172-19 (3 pages).

The information contained therein is hereby noted and account of same will be taken in our quoted cost.

This information was received on the _____ day of _____, 20_____.

Signature

Name (Printed)

Company Name

***NOTE: You are required to acknowledge this addendum with your Tender submission.**

**PLEASE FAX BACK TO (519) 255-9891 OR E-MAIL to: purchasing@citywindsor.ca
SIGNED ACKNOWLEDGEMENT SHEET ASAP**

Attn: Purchasing Department