

## SCHEDULE I

The person to whom a permit under Section 8 of the Act is issued shall notify the *Chief Building Official* or, where a *Registered Code Agency* is appointed under the Act in respect of the *construction* to which the notice relates, the *Registered Code Agency* of:

- a) readiness to *construct* footings,
- b) substantial completion of footings and *foundations* prior to commencement of backfilling,
- c) substantial completion of structural framing and ductwork and piping for heating and *air-conditioning* systems, if the *building* is within the scope of Part 9 of Division B,
- d) substantial completion of structural framing and roughing-in of heating, ventilation, *air-conditioning* and air-contaminant extraction equipment, if the *building* is not a *building* to which Clause (c) applies,
- e) substantial completion of insulation, *vapor barriers* and *air barriers*,
- f) substantial completion of all required *fire separations* and *closures* and all fire protection systems including standpipe, sprinkler, fire alarm and emergency lighting systems,
- g) substantial completion of fire access routes,
- h) readiness for inspection and testing of:
  - (i) *building sewers* and *building drains*,
  - (ii) *water service pipes*,
  - (iii) *fire service mains*,
  - (iv) *drainage systems* and *venting systems*,
  - (v) the *water distribution system*, and
  - (vi) *plumbing fixtures* and *plumbing appliances*,
- i) readiness for inspection of suction and gravity outlets, covers and suction piping servicing outlets, of *outdoor pool* described in Clause 1.3.1.1.(1)(j) of Division A, a *public pool* or a *public spa*,
- j) substantial completion of the circulation/*recirculation system* of an *outdoor pool* described in Clause 1.3.1.1.(1)(j) of Division A, a *public pool* or *public spa* and substantial completion of the pool before it is first filled with water,
- k) readiness to *construct* the *sewage system*,
- l) substantial completion of the installation of the *sewage system* before the commencement of backfilling,
- m) substantial completion of installation of *plumbing* not located in a structure, before the commencement of backfilling, and
- n) completion of *construction* and installation of components required to permit the issue of an occupancy permit under Sentence 1.3.3.1.(2) or to permit occupancy under Sentence 1.3.3.2.(1), if the *building* or part of the *building* to be occupied is not fully completed.